

Cost Breakdown

Portable Cricket Wicket

Supplied, Delivered & Installed

Centre Wicket

- â€¢ 1 x Install concrete slab 2.8m wide x 28m length, Excavate 1% fall for drainage, F82 Reo mesh, 25 MPa concrete 100mm thick, steel trowel finish
- â€¢ 1 x Gabba Grass 10mm SUPER SHIELD 300 2.8m wide x 28m length installed. Wickets feature a 50mm slab perimeter on edges (surface does not extend over concrete sides) for protection during maintenance and edging
- â€¢ 3 x Adhesive 20lt

Total cost - \$28,995 + GST

Drop In Wicket

- â€¢ Supply & install 1 Gabba Drop in synthetic wicket 11 x 2.4m wide x 2.0 long custom concrete panels.
- â€¢ Finished slab of 22m long x 2.4m wide.
- â€¢ Supply & install 1 Gabba Grass portable synthetic wicket 22m x 2.4m □
- â€¢ Senior and Junior line marking
- â€¢ The Turf area 22.2m x 2.6m x 50mm deep is to be cut out, levelled & prepared by school.
- â€¢ Lifting slings supplied for future installations & removals.
- â€¢ Portable stumps with flat base are to be used

□Note: As for preparation a small amount of topsoil is removed to allow for the panels to be □installed (approx. 80mm) deep x the width and length of the wicket. Each panel is about 800kg providing good body to the bounce and play of the wicket with the Gabba Grass surface rolled out over the levelled concrete. A standard permanent wicket is 100mm in thickness vs drop-in wicket 60m

Total - \$44,995 + GST

AFL Cover on existing concrete slab

- â€¢ Supply and installation of 25mm Shock pad to meet AFL requirements
- â€¢ Supply and install of 60mm synthetic turf with rubber infill
- â€¢ Grass meets both AFL/FIFA Requirements.
- â€¢ Supply and install rubber infill groomed in evenly across the surface
- â€¢ Each section to be seam taped & glued with adhesive to ensure no movement.
- â€¢ The important factor is to meet Critical fall height requirement AS/ANS4422:1996.
- â€¢ Installation Guide

□â€¢ Total - \$24980 + GST

□â€¢ Supply Only - \$19,980 + GST



Terms & Conditions

Payment terms: 50% deposit on purchase order, 25% on supply of materials on site and final 25% payment on completion and sign off.

Excludes: Council requirements (DA & BA) – Ex Gabba works.

CONDITIONS OF QUOTATION:

1. Please note that specifics of the quotation including prices and quantities are subject to confirmation prior to commencement of any work. Prices quoted cover only services nominated.
2. This quotation remains valid for 30 days from the quotation date.
3. If our quotation is accepted, work will be undertaken by employees of Gabba Sporting Products and /or our nominated sub-contractors.
4. The conditions of offer are shown in our quotation and our offer does not imply our willingness to enter into a sub-contract agreement containing conditions that differ from our offer.
5. All variations to contract must be made in writing, signed and approved by an authorised representative prior to additional work commencing.
6. Gabba Sporting Products has built its name on quality products & workmanship, all care will be taken whilst working on site. We do not accept any responsibility for any damage to buildings, services or surrounding landscapes as we will be working in conjunction with the property engineers & stakeholders.
7. It is the client's responsibility to mark out boundaries and/or have the boundary surveyed, and services such as Phone, Power, Water & Gas must be located by the client.
8. To facilitate vehicle and machine entry to the site, a suitable path is to be nominated by the client. The client is to provide ground protection mats in place if the path is soft & likely to be damaged.
9. Unless otherwise specified, quotations are based on standard soil conditions for excavation. In the event of rock, hard fill or foreign material being encountered, further costs as required for excavation / earthwork will be applied.
10. This quote is subject to site inspection. If the work site is found to contain unforeseen obstacles, resulting in need for additional earthwork, structural support etc., this quote will no longer be valid and a new quote will be issued.
11. All soil lifted during excavation will be moved within the grounds, no soil will be removed from the property, a suitable location will be arranged with the grounds staff prior to excavation work starting.
12. Whilst every effort is made to complete the works within a timely manner, deviation from the anticipated time frame may be encountered in unfavourable weather conditions or where unforeseen obstacles are encountered within the site.
13. Site specific inductions that exceed thirty (30) minutes in length will incur a charge based on our hourly rate.
14. In the event of a dispute, the client agrees to provide details of the dispute in writing within 7 days of receipt of our invoice. If no details are provided within this time, all due monies are to be paid as per our agreed trading terms.
15. Notwithstanding the Terms & Conditions outlined above, these terms will not negate any state or federal regulation in any way.
16. It is the customer's responsibility to ensure sufficient access, equipment, and personnel are available to unload the entire order from the truck.

Accepting the above works, items, notes & payment terms

Full Name: _____ Signature: _____ Date: _____

Kind Regards Amanda Willcox

